

**Addendum No. 1**

**Project: Pavement Repairs**

**Tender Reference: RFT 2026-02**

**Date: March 26, 2026**

The following change to the Bid Documents is effective immediately and will form part of the Bid Documents.

This addendum is issued to add clarity to item F.1 and F.2 in the Schedule of Prices.

**F.1**

Shall encompass approximately 1620 square meters of existing gravel trail in the Trails of West St. Paul Development. Existing 20mm crushed limestone base shall be reshaped as necessary and compacted. 20mm crushed limestone to be added as necessary to maintain a consistent shape. Asphalt shall be placed in two equal lifts to a final thickness of 75mm and final width of 1.83m.

**F.2**

Shall encompass approximately 150 square meters of existing gravel trail located at 100 Parkview Pointe Drive, West St. Paul. The existing trail shall be excavated to a depth of 0.3m and width of 2m. Place minimum 200 gsm geotextile to a width of 2m along foundation excavation. Excavate and place 75mm thick pipe bedding for 300mm x 5m 16 gauge corrugated steel pipe in existing drainage ditch. Ensure positive drainage of pipe. Backfill pipe to haunches with 20mm down crushed limestone. Place and compact 20mm down crushed limestone base to a finished thickness of 300mm. Place and compact 75mm asphalt in two equal lifts to a finished width of 1.83m



F.2



3550 Main Street  
WEST ST. PAUL, MB. R4A 5A3  
Ph: 204-338-0306 Fax: 204-334-9362